

Himalayan Distillery Limited

Scope of Work: Civil Construction of Plant (CPU)

Location: Birgunj 21, Parsa Nepal

Quotation submitted by:

Address:

Contact person:

Contact Details:

S.N.	Descriptions of Works	Unit	Quantity	Rate (NRs.)	Amount (NRs.)	Remarks
1	Site clearance work:					
1.1	Site clearance work before and after construction including layout of the building excluding temporary protection work around the construction site. Including construction of site office, safety measured works etc.	JOB	1			
2	Earthwork:					
2.1	Earth work in excavation over areas/ foundation trenches in all kinds of soils and at specified depths for basements, footings, foundations, tanks, reservoirs, etc. including dressing, hand ramming and making profiles etc. including dressing, hand ramming and making profiles etc. including disposal of surplus earth as directed by Engineer.	Cu.M.	59.95			
2.2	Earthfilling: E/W in back filling by Earth in necessary proper compaction with water sprinkle on layer by layer for compaction as per design, specification & instruction of engineer.	Cu.M.	23.98			
3	Boulder Soling					
	Providing and laying Boulder Soling of 250mm thick in one layer with sand binding between the gap in perfect line & level, all complete as per drawings, approval of Engineer.	Cu.M.	29.98			
4	P.C.C. (1:3:6) Work					
	Providing and laying cement concrete 1:3:6 (1 cement: 3 coarse sand :6 graded stone aggregate 40mm down size) under foundation footing in line and level with proper curing, all complete as per drawing.	Cu.M.	11.24			
5	RCC M20 Grade Concreting					
	Plain cement concrete for RCC shearwall, column, beam, slabs, lintels, wall footing and all types of RCC works with cement, sand and stone ballast 20mm & down including mixing, laying, finishing & curing as per drawing, specification and instruction of consultant.	Cu.M.	60.91			
6	TMT Reinforcement Bar (Fe-500) works:					
	Providing and laying steel reinforcement in all reinforced concrete work Including supply, handling, cutting, removal of rust if required by wire brush, bending, fabricating and placing in position to the shape and profile required drawing, tying with 16 SWG annealed steel wire and with proper cover blocks, supports, chairs, spacer bars etc. and approval off Engineer, all complete in all respects for all heights.	KGs.	1601.37			

S.N.	Descriptions of Works	Unit	Quantity	Rate (NRs.)	Amount (NRs.)	Remarks
7	Formwork:					
	Centring, shuttering for all types of reinforced cement concrete works including strutting, propping and removal of form works etc. all as per Architectural Drawings. (quoted rate to include making grooves, chamfers wherever shown in the drawings for beam, lintel, band, slab projection).	Sq.M	311.75			
8	Brickwork:					
	Providing and laying 9" (230mm) or more thick first class Chimney Bhatta local made brick work in 10mm thick cement sand mortar (1:6 ratio) course for external wall including the cost of scaffolding, curing and raking out the joints wherever required, using approved size and quality of bricks excluding normal reinforcement as per drawing and instruction of site engineer, all complete.	Cu.M.	7.36			
9	Cement/Sand Plaster work:					
	Internal/External Wall Plaster: Plaster work in 1:5 cement, sand mortar (12-20mm thick) in accurate line and level including wetting the surface, curing the work and fixing chicken wire mesh in junction between beam and wall all complete as per drawing specification and instruction of the Engineer.	Sq.M	68.82			
10	Painting Work:					
	Washable Distemper Paints: Supplying & applying premium grade Acrylic emulsion paints including 2 coats of wall putty of JK Asian or Berger or equivalent with one coat primer and two coats of paints to give an even and uniform shade as per specification and instruction of the Engineer.	Sq.M	68.82			
11	Metal Work :					
	Supplying and fabricating all metal members like pipe, C-channel, beam, rafter etc. of any shape and size with straightened and properly welded and screwed 11 to the plate as per design and instruction of Engineer. Welding joint must be smooth and all members must be painted with primer. Scaffolding rate should be included in quoted rate, no extra for scaffolding will be paid.					
	a) Truss (Purlin, Wind bracing, Rafter)	KGs.	2465.1			
	b) Post 75x150mm I Beam	Nos.	545.89			
	c) Post C-Channel (50x100x5)	KGs.	203.31			
	d) Base Plate 8mm	KGs.	20.01			
12	Roofing Works					
	a) Supplying and fixing 24 gauge colour CGI sheet roofing work as per approved colour and proper lapping in perfect line and level including all required hardware as per design and instruction of Engineer.	Sq.M	112.05			

S.N.	Descriptions of Works	Unit	Quantity	Rate (NRs.)	Amount (NRs.)	Remarks
13	IPS flooring works:					
	Providing & Laying 25-50mm thick (1:2:4) cement, sand, stone chips-concrete and finishing the surface with 1:1 cement sand neat finish including hacking & cleaning of floor surface all complete, as per drawing, specification & instruction of Engineer.	Sq.M	134.44			
14	Punning Work:					
	Applying paste of 1:1 ration of cement and sand on shear wall or wherever required in perfect line and level with smooth finish as per instruction of Engineer.	Sq.M	200			
15	Water Proof work:					
	Applying water proofing coating coating of Evercreate, USA or equivalent approved make as Water proofing treatment on RCC wall, rooftop, suncken slab, Bathroom floors etc. areas as appropriate method suggest by manufactrurer specification with protective layer, all complete.	Sq.M	187.2			
	Sub Total					
	Add 13% VAT					
	Grand Total					

*Himalayan Distillery Limited, reserves all the rights to accept or reject any or all the quotations fully or partially without assigning any reason whatsoever and is not bound to accept the lowest quotation.

Sign & Company/Firm seal :