

Notice published date: 6th Oct. 2024 (Arnik Abhijon)

INVITATION FOR QUOTATION

Himalayan Distillery Ltd. invites sealed quotation for 'Land and Road Development Work' from the interested eligible and resourceful construction company having sufficient resources & experience in execution of similar type of works as details here under.

The complete set of documents can be received at free of cost from its Contact Office at Jawalakhel, Lalitpur or can be downloaded from the website of the company "www.himalayandistillery.com".

Interested construction company/firm must submit sealed quotation (hardcopy) at following address within 17th October, 2024. Proposals received after the deadline will not be considered for further evaluation.

1. Project Location: Soludhuhkunda Municipality-8, Pattale, Solukhumbu, Nepal

2. Access road of site: Connected with Sagarmatha Highway

3. Scope of Work: Supply of materials & services of the work

4. Required Document:

- Valid company/firm registration certificate, Memorandum of Association (MoA) & Articles of Association (AoA), latest share structure (Share Lagat) latest company update certificate (Company Adhyawodhik)
- VAT certificate
- Latest tax clearance certificate.
- Company/Firm Profile

4. Eligibility Criteria:

- **Experience:** Successful completion of minimum two project within last two years (Job completion certificate duly issued by the employer should be submitted with the document).

Further information can be obtained from office of the company at Jawalakhel, Lalitpur, Nepal.



Himalayan Distillery Ltd.

Contact Office, Uttar Bagaicha Marg, Jawalakhel, Lalitpur, Nepal
Contact No.: 01-5427465

Himalayan Distillery Limited, reserves all the rights to accept or reject any or all the quotations fully or partially without assigning any reason whatsoever and is not bound to accept the lowest quotation

Himalayan Distillery Limited
Jawalakhel, Lalipur

BILL OF QUANTITIES

Project : Land and Road Development Works
Location: Soluhudhkunda Municipality-8, Pattele, Solukhumbu, Nepal

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
A	CIVIL WORK						
1.00	Site Clearance Works: Clearing the required area of the Site of all the top soil, vegetation, roots and other unuseful materials including leveling, removing bushes, trees; stacking the useful items in specified space and disposing other items as per drawing, specifications & instruction of site engineer all complete.	Sqm	1,541.22				
2.00	Hydraulic Excavation: Excavation in any kind of soils at all levels for all types of structures, including shoring, strutting, pumping and bailing out water; dewatering if any so as to keep foundations in dry condition at any stage of work, drain the water away from the site through sub drain and connecting into main drain, stacking the excavated earth at proper place near site for refill using mechanical means including disposal of excavated soil to the designated dumping yard with lead and lift as per drawing, specifications & instruction of site engineer all complete.	Cum	3,184.94				
3.00	Earth Filling Works: Earth work in filling with excavated soil in site by spreading of soil in 150 mm thick layer, including watering, ramming with proper compaction, supply of filling materials within 10m distance all complete as per drawings, specifications and instructions of the Engineer in charge.	Cum	1,217.05				

Himalayan Distillery Limited
Jawalakhel, Lalitpur

BILL OF QUANTITIES

Project : Land and Road Development Works

Location: Soluhdhukunda Municipality-8, Patte, Solukhumbu, Nepal

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
4.00	PCC Work: Plain Cement Concrete (P.C.C.) in 1:2:4 (cement:sand:aggregate) work below footing and coping on grade with cement, sand and gravel sizes of proper grading from 10mm to 20mm including mixing, laying, finishing to approved level, line and dimensions with curing including supplying of all materials, labour, transportation, load unload all complete as per drawings, specifications and instructions of the Engineer in charge.	Cum	29.79				
5.00	Formwork: Providing, Laying & Fixing, Centering and shuttering with approved wood for all kinds of R.C./P.C.C works including all necessary propping, scaffolding, staging, supporting, dismantling and clearing from the site, transportation, load unload all complete as per design drawings, specifications and instruction of the site engineer .	Sqm	73.76				
6.00	Stone masonry work in (1:6) cement sand mortar with approved quality stone upto ground floor in perfect line and level including wetting the stone, packing the joints and curing, with necessary scaffolding work, including supplying of all materials, transportation, labour, lead and lift work as per design, drawings, specifications and instructions of the site engineer all complete.	cum	471.65				

Himalayan Distillery Limited
Jawalakhel, Lalitpur

BILL OF QUANTITIES

Project : Land and Road Development Works
Location: Soluhudhkunda Municipality-8, Pattele, Solukhumbu, Nepal

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
7.00	Pointing Works on stone masonry: Supplying and laying false ruled pointing works with (1:1) cement sand mortar on stone masonry wall surfaces of good finish, cleaning and wetting the surface and curing the work including transportation, load unload all complete as per specification and approval of site Engineer.	Sq.m	648.28				
8.00	HDPE Pipe: Supplying and laying 100 mm diameter high density polyethylene pipe (1.703 Avg. wt. kg/m) staggered at 1m c/c for weep hole of Retaining wall including transportation, load unload all complete as per specification, instruction and drawing and approval of engineer.	R.m	458.85				
9.00	Geotextile Membrane: Supplying and laying Geotextile Membrane around the pipe of weep hole of Retaining wall including transportation, load unload as per design, drawings, specifications and instructions of the site engineer all complete.	Sq.m	34.64				
B	Road Construction Works		-				
10.00	Sub-Grade Preparation Work : Sub grade preparation work with 100mm thick earthwork in excavation work including transportation, load unload and disposal as per DOR Standard specification for Road and Bridge and approval of engineer all complete.	Sqm	1,138.64				

Himalayan Distillery Limited
Jawalakhel, Lalitpur

BILL OF QUANTITIES

Project : Land and Road Development Works
Location: Soluhdhukunda Municipality-8, Pattele, Solukhumbu, Nepal

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
11.00	Sub-Base Course Preparation Works: Providing, laying, spreading, watering, levelling, and compaction of natural sand gravel subbase work including lead and lift, transportation as per DOR Standard specification for Road and Bridge and approval of engineer all complete.	Cum	296.05				
12.00	Base Course Preparation Works: Providing, laying, spreading, watering, levelling and compaction of crusher run materials for base course including lead and lift, transportation as per DOR Standard specification for Road and Bridge and approval of engineer all complete.	Cum	170.80				
Total Amount=							NRs.
VAT (@13%)=							NRs.
Grand Total Amount Including VAT (In Words)=							NRs.
Grand Total Amount Including VAT (In Figures)=							NRs.